

Timer module, 200-240VAC, 5-100s, off-delayed

Part no.	DILM32-XTED11-100(RAC240)
Catalog No.	104948
Alternate Catalog No.	XTCEXTED100C11B
EL-Nummer (Norway)	4130418



Powering Business Worldwide™

Delivery program

Product range		Accessories
Accessories		Timer modules
Description		Off-delayed, auxiliary voltage-free Cannot be combined with top mounting auxiliary contacts Incl. suppressor circuits
U _S		200 - 240 V AC 50/60 Hz
Time range		5 - 100 s
For use with		DILM7 - DILM38 DILMP20 DILMP32-DILMP45 DILA DILMF7 DILMF11 DILMF14 DILMF25 DILMF32

Technical data

General			
Standards			DIN EN 61812, IEC/EN 60947, VDE 0660, UL, CSA
Lifespan, mechanical			
AC operated	Operations	x 10 ⁶	3
DC operated	Operations	x 10 ⁶	3
Climatic proofing			Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30
Ambient temperature			
Open		°C	-25 - +60
Enclosed		°C	-25 - 40
Storage		°C	-40 - 80
Mounting position			As required, except suspended
Mechanical shock resistance (IEC/EN 60068-2-27)			
Half-sinusoidal shock, 10 ms			
N/O contact		g	6
N/C contact		g	6
Degree of Protection			IP20
Protection against direct contact when actuated from front (EN 50274)			Finger and back-of-hand proof
Weight		kg	0.08
Terminal capacities		mm ²	
Solid		mm ²	1 x (0.75 - 2.5) 2 x (0.75 - 1.5)
Flexible with ferrule		mm ²	1 x (0.75 - 1.5) 2 x (0.75 - 1.5)
Solid or stranded		AWG	18 - 14
Terminal screw			M3.5
Pozidriv screwdriver		Size	2
Standard screwdriver		mm	0.8 x 5.5 1 x 6
Max. tightening torque		Nm	1.2
Contacts			
Rated impulse withstand voltage	U _{imp}	V AC	4000
Overvoltage category/pollution degree			III/3

Rated insulation voltage	U_i	V AC	250
Rated operational voltage	U_e	V	250
Rated operational current	I_e	A	
AC-15			
220 V 230 V 240 V	I_e	A	3
DC-13			
DC-13 L/R - 15 ms			
Contacts in series:		A	
1	24 V	A	1
1	60 V	A	0.2
1	110 V	A	0.2
1	220 V	A	0.1
DC L/R \leq 50 ms			
Contacts in series:		A	
1	24 V	A	1
1	60 V	A	0.2
1	110 V	A	0.2
1	220 V	A	0.1
DC-13 L/R - 300 ms			
Contacts in series:		A	
1	24 V	A	1
1	60 V	A	0.2
1	110 V	A	0.2
1	220 V	A	0.1
Safe isolation to EN 61140			
between coil and auxiliary contacts		V AC	250
between the auxiliary contacts		V AC	250
Conventional thermal current	I_{th}	A	4
Short-circuit rating without welding			
max. fuse		A gG/gL	4

Magnet systems

Voltage tolerance			
Pick-up voltage		$\times U_s$	
AC operated		V AC	
	Pick-up	$\times U_c$	0.85 - 1.1
DC operated	Pick-up	$\times U_c$	
	Pick-up	$\times U_c$	0.7 - 1.2
Power consumption			
60 °C	Sealing	VA	2
AC operated	Sealing	W	1.8
duty factor		% DF	100
Maximum operating frequency		Ops./h	
Max. operating frequency		Ops/h	3600
Can be combined with auxiliary contact		Ops/h	360
Conventional thermal current $I_{th} = I_e$ AC-1			
On-delayed		ms	< 50
Off-delayed		ms	< 200
AC operated 50 Hz	Deviation	%	< 5
Recovery time (after 100% time delay)		ms	70
contact changeover time			
DILM32-XTEE11/DILM32-XTED11	t_u	ms	10
DILM32-XTEY20	t_u	ms	50

Notes

Notes For rated operational current: Making and breaking conditions to DC-13, L/R constant as stated
 Max. fuses for short-circuit protection: Transparent overlay "Fuses" for time/current characteristics (please enquire)
 For pick-up voltage, DC operated: Pure DC, AC bridge rectifier or smoothed double-wave rectification.

Rating data for approved types

Auxiliary contacts			
Pilot Duty			
AC operated			B300
DC operated			R300
General Use			
AC	V	240	
AC	A	5	
DC	V	24	
DC	A	5	
Short Circuit Current Rating	SCCR		
Basic Rating			
SCCR	kA	5	
max. Fuse	A	125	
max. CB	A	125	
480 V High Fault			
SCCR (fuse)	kA	10/100	
max. Fuse	A	125/70 Class J	
SCCR (CB)	kA	10/65	
max. CB	A	50/32	
600 V High Fault			
SCCR (fuse)	kA	10/100	
max. Fuse	A	125/125 Class J	
SCCR (CB)	kA	10/22	
max. CB	A	50/32	

Design verification as per IEC/EN 61439

Technical data for design verification			
Rated operational current for specified heat dissipation	I _h	A	0
Heat dissipation per pole, current-dependent	P _{vid}	W	0
Equipment heat dissipation, current-dependent	P _{vid}	W	0
Static heat dissipation, non-current-dependent	P _{vs}	W	1.8
Heat dissipation capacity	P _{diss}	W	0
Operating ambient temperature min.		°C	-25
Operating ambient temperature max.		°C	60
IEC/EN 61439 design verification			
10.2 Strength of materials and parts			
10.2.2 Corrosion resistance			Meets the product standard's requirements.
10.2.3.1 Verification of thermal stability of enclosures			Meets the product standard's requirements.
10.2.3.2 Verification of resistance of insulating materials to normal heat			Meets the product standard's requirements.
10.2.3.3 Verification of resistance of insulating materials to abnormal heat and fire due to internal electric effects			Meets the product standard's requirements.
10.2.4 Resistance to ultra-violet (UV) radiation			Meets the product standard's requirements.
10.2.5 Lifting			Does not apply, since the entire switchgear needs to be evaluated.
10.2.6 Mechanical impact			Does not apply, since the entire switchgear needs to be evaluated.
10.2.7 Inscriptions			Meets the product standard's requirements.
10.3 Degree of protection of ASSEMBLIES			Does not apply, since the entire switchgear needs to be evaluated.
10.4 Clearances and creepage distances			Meets the product standard's requirements.
10.5 Protection against electric shock			Does not apply, since the entire switchgear needs to be evaluated.
10.6 Incorporation of switching devices and components			Does not apply, since the entire switchgear needs to be evaluated.
10.7 Internal electrical circuits and connections			Is the panel builder's responsibility.
10.8 Connections for external conductors			Is the panel builder's responsibility.
10.9 Insulation properties			
10.9.2 Power-frequency electric strength			Is the panel builder's responsibility.
10.9.3 Impulse withstand voltage			Is the panel builder's responsibility.

10.9.4 Testing of enclosures made of insulating material		Is the panel builder's responsibility.
10.10 Temperature rise		The panel builder is responsible for the temperature rise calculation. Eaton will provide heat dissipation data for the devices.
10.11 Short-circuit rating		Is the panel builder's responsibility. The specifications for the switchgear must be observed.
10.12 Electromagnetic compatibility		Is the panel builder's responsibility. The specifications for the switchgear must be observed.
10.13 Mechanical function		The device meets the requirements, provided the information in the instruction leaflet (IL) is observed.

Technical data ETIM 8.0

Relays (EG000019) / Timer block (EC002060)

Electric engineering, automation, process control engineering / Low-voltage switch technology / Component for low-voltage switching technology / Timer block attachment (ecl@ss10.0.1-27-37-13-08 [ACN996011])

Switching function		Time-delay dropped out
Setting time	s	5 - 100
Number of contacts as normally open contact		1
Number of contacts as normally closed contact		1
Number of contacts as change-over contact		0
Operating principle		Electronic